

**Revised Bid Schedule  
2017 STREET RESURFACING PROJECT  
City of Tifton, Georgia**

**Bid Summary**

<b>STREET NAME</b>	<b>FROM</b>	<b>TO</b>	<b>BASE BID AMOUNT</b>
16th Street	Love Avenue	Tyson Avenue	\$ _____
Fulwood Drive	Central Avenue	Outerbridge Road	\$ _____
Goff Street	20th Street	22nd Street	\$ _____
Eastwood Drive	Newton Drive	Windsor Drive	\$ _____
Pineview Avenue	8th Street	12th Street	\$ _____
Park Avenue	12th Street	20th Street	\$ _____
40th Street	Tift Avenue	Carmichael Drive	\$ _____
9th Street	Central Avenue	Park Avenue	\$ _____
Emmett Drive	20th Street	28th Street	\$ _____
11th Street	Timmons Drive	Ridge Avenue	\$ _____
Ridge Avenue	12th Street	14th Street	\$ _____
<b>TOTAL AMOUNT OF PROJECT BASE BID</b>			<b>\$ _____</b>

**CONTRACTOR'S NAME:** \_\_\_\_\_

BID SCHEDULE CONTINUED

**2017 LMIG PROJECT  
16th Street**

ITEM NO.	DOT REF. No.	DESCRIPTION	Quantity Unit	UNIT PRICE	EXTENSION
1	151	Mobilization/Demobilization	1 LS		
2		Insurance/Bonds	1 LS		
3	150	Traffic control, complete	1 LS		
4	413	Bituminous Tack Coat	1421 GAL		
5	402	Recycled Asphalt Conc, 9.5 mm, Type I, Superpave, GP 1 or 2, incl. Bitum Mat'l, 125 lb/sy	592 TN		
6	402	Recycled Asphalt Conc, Leveling	148 TN		
7	653	Solid Stop Bar, 24" wide, White	80 LF		
8	653	Double Solid Traffic Stripe, Yellow	800 LF		
9	653	Skip Traffic Stripe, Yellow	2385 LF		
10	653	Solid Traffic Stripe, White, Parking	360 LF		
11	611	Adjust Manhole to finished grade	3 EA		
12	611	Adjust gas valves and water valves to finished grade	8 EA		
TOTAL AMOUNT OF 16th STREET BID					

**2017 LMIG PROJECT  
Fulwood Drive**

ITEM NO.	DOT REF. No.	DESCRIPTION	Quantity Unit	UNIT PRICE	EXTENSION
1	151	Mobilization/Demobilization	1 LS		
2		Insurance/Bonds	1 LS		
3	150	Traffic control, complete	1 LS		
4	413	Bituminous Tack Coat	1176 GAL		
5	424	Single Surface Treatment, Stn Size 7, GP 2 only	7843 SY		
6	402	Recycled Asphalt Conc, 9.5 mm, Type I, Superpave, GP	490 TN		
7	653	Skip Traffic Stripe, Yellow	2941 LF		
TOTAL AMOUNT OF FULWOOD DRIVE BID					

ALTERNATE BID

ITEM NO.	DOT REF. No.	DESCRIPTION	Quantity Unit	UNIT PRICE	EXTENSION
8	415	Asphaltic concrete open graded crack relief interlayer (Alternate for Single Surface Treatment)	432 TN		
TOTAL AMOUNT OF FULWOOD DRIVE ALTERNATE BID					

BID SCHEDULE CONTINUED

**2017 LMIG PROJECT  
Goff Street**

<b>NO.</b>	<b>DOT REF. No.</b>	<b>DESCRIPTION</b>	<b>Quantity Unit</b>	<b>UNIT PRICE</b>	<b>EXTENSION</b>
1	151	Mobilization/Demobilization	1 LS	_____	_____
2		Insurance/Bonds	1 LS	_____	_____
3	150	Traffic control, complete	1 LS	_____	_____
4	413	Bituminous Tack Coat	332 GAL	_____	_____
5	424	Single Surface Treatment, Stn Size 7, GP 2 only	2212 SY	_____	_____
6	402	Recycled Asphalt Conc, 9.5 mm, Type I, Superpave, GP 1 or 2, incl. Bitum Mat'l, 125 lb/sy	138 TN	_____	_____
7	653	Solid Stop Bar, 24" wide, White	32 LF	_____	_____
8	653	Double Solid Traffic Stripe, Yellow	200 LF	_____	_____
9	653	Skip Traffic Stripe, Yellow	422 LF	_____	_____
10	611	Adjust Manhole to finished grade	2 EA	_____	_____
11	611	Adjust gas valves and water valves to finished grade	1 EA	_____	_____
12		Roadway repair, base & wearing surface, 0-2 ft depth	20 SY	_____	_____
13	441	Remove & replace concrete curb & gutter, complete	50 LF	_____	_____
<b>TOTAL AMOUNT OF GOFF STREET BID</b>				_____	_____

ALTERNATE BID

<b>ITEM NO.</b>	<b>DOT REF. NO.</b>	<b>DESCRIPTION</b>	<b>Quantity Unit</b>	<b>UNIT PRICE</b>	<b>EXTENSION</b>
14	415	Asphaltic concrete open graded crack relief interlayer (Alternate for Single Surface Treatment)	122 TN	_____	_____
<b>TOTAL AMOUNT OF GOFF STREET ALTERNATE BID</b>				_____	_____

BID SCHEDULE CONTINUED

**2017 LMIG PROJECT  
Eastwood Drive**

NO.	DOT REF. No.	DESCRIPTION	Quantity Unit	UNIT PRICE	EXTENSION
1	151	Mobilization/Demobilization	1 LS		
2		Insurance/Bonds	1 LS		
3	150	Traffic control, complete	1 LS		
4	413	Bituminous Tack Coat	514 GAL		
5	424	Single Surface Treatment, Stn Size 7, GP 2 only	3425 SY		
6	402	Recycled Asphalt Conc, 9.5 mm, Type I, Superpave, GP 1 or 2, incl. Bitum Mat'l, 125 lb/sy	214 TN		
7	653	Solid Stop Bar, 24" wide, White	44 LF		
8	653	Double Solid Traffic Stripe, Yellow	800 LF		
9	653	Skip Traffic Stripe, Yellow	600 LF		
10	611	Adjust Manhole to finished grade	3 EA		
TOTAL AMOUNT OF EASTWOOD DRIVE BID					

ALTERNATE BID

ITEM NO.	DOT REF. NO.	DESCRIPTION	Quantity Unit	UNIT PRICE	EXTENSION
11	415	Asphaltic concrete open graded crack relief interlayer (Alternate for Single Surface Treatment)	189 TN		
TOTAL AMOUNT OF EASTWOOD DR. ALTERNATIVE BID					

BID SCHEDULE CONTINUED

**2017 LMIG PROJECT  
Pineview Avenue**

NO.	DOT REF. No.	DESCRIPTION	Quantity Unit	UNIT PRICE	EXTENSION
1	151	Mobilization/Demobilization	1 LS	_____	_____
2		Insurance/Bonds	1 LS	_____	_____
3	150	Traffic control, complete	1 LS	_____	_____
4	413	Bituminous Tack Coat	487 GAL	_____	_____
5	402	Recycled Asphalt Conc, 9.5 mm, Type I, Superpave, GP 1 or 2, incl. Bitum Mat'l, 125 lb/sy	203 TN	_____	_____
6	402	Recycled Asphalt Conc, Leveling	51 TN	_____	_____
7	653	Solid Stop Bar, 24" wide, White	22 LF	_____	_____
8	653	Double Solid Traffic Stripe, Yellow	400 LF	_____	_____
9	653	Skip Traffic Stripe, Yellow	928 LF	_____	_____
10	611	Adjust Manhole to finished grade	4 EA	_____	_____
TOTAL AMOUNT OF PINEVIEW AVENUE BID				_____	_____

**2017 LMIG PROJECT  
Park Avenue**

ITEM	DOT REF. No.	DESCRIPTION	Quantity Unit	UNIT PRICE	EXTENSION
1	151	Mobilization/Demobilization	1 LS	_____	_____
2		Insurance/Bonds	1 LS	_____	_____
3	150	Traffic control, complete	1 LS	_____	_____
4	413	Bituminous Tack Coat	1013 GAL	_____	_____
5	402	Recycled Asphalt Conc, 9.5 mm, Type I, Superpave, GP	422 TN	_____	_____
6	653	Solid Stop Bar, 24" wide, White	50 LF	_____	_____
7	653	Double Solid Traffic Stripe, Yellow	800 LF	_____	_____
8	653	Skip Traffic Stripe, Yellow	1323 LF	_____	_____
9	653	Solid Traffic Stripe, White, Parking	550 LF	_____	_____
10	611	Adjust Manhole to finished grade	2 EA	_____	_____
11	611	Adjust gas valves and water valves to finished grade	3 EA	_____	_____
TOTAL AMOUNT OF PARK AVENUE BID				_____	_____

BID SCHEDULE CONTINUED

**2017 LMIG PROJECT  
40th Street**

NO.	DOT REF. No.	DESCRIPTION	Quantity Unit	UNIT PRICE	EXTENSION
1	151	Mobilization/Demobilization	1 LS		
2		Insurance/Bonds	1 LS		
3	150	Traffic control, complete	1 LS		
4	413	Bituminous Tack Coat	509 GAL		
5	424	Single Surface Treatment, Strn Size 7, GP 2 only	6780 SY		
6	402	Recycled Asphalt Conc, 9.5 mm, Type I, Superpave, GP 1 or 2, incl. Bitum Mat'l, 125 lb/sy	424 TN		
7	653	Solid Stop Bar, 24" wide, White	21 LF		
8	653	Double Solid Traffic Stripe, Yellow	400 LF		
9	653	Skip Traffic Stripe, Yellow	2450 LF		
TOTAL AMOUNT OF 40th STREET BID					

ALTERNATE BID

ITEM NO.	DOT REF. NO.	DESCRIPTION	Quantity Unit	UNIT PRICE	EXTENSION
10	415	Asphaltic concrete open graded crack relief interlayer (Alternate for Single Surface Treatment)	373 TN		
TOTAL AMOUNT OF 40th STREET ALTERNATE BID					

BID SCHEDULE CONTINUED

**2017 LMIG PROJECT  
9th Street**

<b>NO.</b>	<b>DOT REF. No.</b>	<b>DESCRIPTION</b>	<b>Quantity Unit</b>	<b>UNIT PRICE</b>	<b>EXTENSION</b>
1	151	Mobilization/Demobilization	1 LS	_____	_____
2		Insurance/Bonds	1 LS	_____	_____
3	150	Traffic control, complete	1 LS	_____	_____
4	413	Bituminous Tack Coat	479 GAL	_____	_____
5	424	Single Surface Treatment, Stn Size 7, GP 2 only	3193 SY	_____	_____
6	402	Recycled Asphalt Conc, 9.5 mm, Type I, Superpave, GP 1 or 2, incl. Bitum Mat'l, 125 lb/sy	200 TN	_____	_____
7	653	Solid Stop Bar, 24" wide, White	21 LF	_____	_____
8	653	Double Solid Traffic Stripe, Yellow	400 LF	_____	_____
9	653	Skip Traffic Stripe, Yellow	227 LF	_____	_____
<b>TOTAL AMOUNT OF 9th STREET BID</b>				_____	_____

ALTERNATE BID

<b>ITEM NO.</b>	<b>DOT REF. NO.</b>	<b>DESCRIPTION</b>	<b>Quantity Unit</b>	<b>UNIT PRICE</b>	<b>EXTENSION</b>
10	415	Asphaltic concrete open graded crack relief interlayer (Alternate for Single Surface Treatment)	176 TN	_____	_____
<b>TOTAL AMOUNT OF 9th STREET ALTERNATE BID</b>				_____	_____

BID SCHEDULE CONTINUED

**2017 LMIG PROJECT  
Emmett Drive**

NO.	DOT REF. No.	DESCRIPTION	Quantity Unit	UNIT PRICE	EXTENSION
1	151	Mobilization/Demobilization	1 LS		
2		Insurance/Bonds	1 LS		
3	150	Traffic control, complete	1 LS		
4	413	Bituminous Tack Coat	1355 GAL		
5	424	Single Surface Treatment, Stn Size 7, GP 2 only	4630 SY		
6	402	Recycled Asphalt Conc, 9.5 mm, Type I, Superpave, GP 1 or 2, incl. Bitum Mat'l, 125 lb/sy	585 TN		
7	402	Recycled Asphalt Conc, Leveling	69 TN		
8	432	Milling 1 1/2 inch depth, 8 ft. wide, at curb for asphalt	4892 SY		
9	653	Solid Stop Bar, 24" wide, White	60 LF		
10	653	Double Solid Traffic Stripe, Yellow	800 LF		
11	653	Skip Traffic Stripe, Yellow	1952 LF		
12	611	Adjust Manhole to finished grade	2 EA		
13	611	Adjust gas valves and water valves to finished grade	7 EA		
14		Roadway repair, base & wearing surface, 0-2 ft depth for tree root damage, incl. removal of soil and roots, backfill material and compaction	170 SY		
15	441	Remove & replace concrete curb & gutter, complete	200 LF		
TOTAL AMOUNT OF EMMETT DRIVE BID					

ALTERNATE BID

ITEM NO.	DOT REF. No.	DESCRIPTION	Quantity Unit	UNIT PRICE	EXTENSION
16	415	Asphaltic concrete open graded crack relief interlayer (Alternate for Single Surface Treatment)	255 TN		
TOTAL AMOUNT OF EMMETT DRIVE ALTERNATE BID					



BID SCHEDULE CONTINUED

**2017 LMIG PROJECT  
11th Street**

<b>NO.</b>	<b>DOT REF. No.</b>	<b>DESCRIPTION</b>	<b>Quantity Unit</b>	<b>UNIT PRICE</b>	<b>EXTENSION</b>
1	151	Mobilization/Demobilization	1 LS	_____	_____
2		Insurance/Bonds	1 LS	_____	_____
3	150	Traffic control, complete	1 LS	_____	_____
4	413	Bituminous Tack Coat	549 GAL	_____	_____
5	402	Recycled Asphalt Conc, 9.5 mm, Type I, Superpave, GP 1 or 2, incl. Bitum Mat'l, 125 lb/sy	229 TN	_____	_____
6	402	Recycled Asphalt Conc, Leveling	57 TN	_____	_____
7	653	Solid Stop Bar, 24" wide, White	75 LF	_____	_____
8	653	Double Solid Traffic Stripe, Yellow	400 LF	_____	_____
9	653	Skip Traffic Stripe, Yellow	1031 LF	_____	_____
10	611	Adjust Manhole to finished grade	8 EA	_____	_____
<b>TOTAL AMOUNT OF 11th STREET BID</b>				_____	_____

BID SCHEDULE CONTINUED

**2017 LMIG PROJECT  
Ridge Street**

<b>NO.</b>	<b>DOT REF. No.</b>	<b>DESCRIPTION</b>	<b>Quantity Unit</b>	<b>UNIT PRICE</b>	<b>EXTENSION</b>
1	151	Mobilization/Demobilization	1 LS	_____	_____
2		Insurance/Bonds	1 LS	_____	_____
3	150	Traffic control, complete	1 LS	_____	_____
4	413	Bituminous Tack	512 GAL	_____	_____
5	424	Single Surface Treatment, Stn Size 7, GP 2 only	3410 SY	_____	_____
6	402	Recycled Asphalt Conc, 9.5 mm, Type I, Superpave, GP 1 or 2, incl. Bitum Mat'l, 125 lb/sy	213 TN	_____	_____
7	653	Solid Stop Bar, 24" wide, White	24 LF	_____	_____
8	653	Double Solid Traffic Stripe, Yellow	200 LF	_____	_____
9	653	Skip Traffic Stripe, Yellow	440 LF	_____	_____
10		Roadway repair, base & wearing surface, 0-2 ft depth for	20 SY	_____	_____
11	441	Remove & replace concrete curb & gutter, complete	50 LF	_____	_____
TOTAL AMOUNT OF RIDGE STREET BID				_____	_____

ALTERNATE BID

<b>ITEM NO.</b>	<b>DOT REF. NO.</b>	<b>DESCRIPTION</b>	<b>Quantity Unit</b>	<b>UNIT PRICE</b>	<b>EXTENSION</b>
12	415	Asphaltic concrete open graded crack relief interlayer (Alternate for Single Surface Treatment)	188 TN	_____	_____
TOTAL AMOUNT OF RIDGE STREET ALTERNATE BID				_____	_____