

## ADDENDUM #1

PROJECT: Leroy Rogers Senior Center Pavement Improvements

ACTION: Changes to Plans and Bid Sheet

DATE: January 2, 2018

The following changes and clarifications are made to the above referenced project:

- 1) Base Bid Item #26 is removed from the Bid Schedule
- 2) Additive/Alternate Bid Item #31 includes all work and material required for the bioretention pond except the plants.
- 3) Reference on the plans to an 1" overlay on the existing pavement is to be replaced by a seal coat meeting GDOT Specification 427.
- 4) The grading for the Base Bid includes a cut volume of approximately 857 yd<sup>3</sup> and a fill volume of about 959 yd<sup>3</sup> including the ditch area. The Add./Alt. Bid has a cut volume of about 32 yd<sup>3</sup> and approximately 51 yd<sup>3</sup> of fill. These volumes are approximate. It is the responsibility of the bidder to determine if undercut soils can be reused as structural fill.
- 5) The bid date remains unchanged.

All bidders shall acknowledge receipt of all addenda issued where indicated on the bid sheets.

**BIDDERS ARE ADVISED THAT IT IS THEIR RESPONSIBILITY TO VERIFY THAT ANY AND ALL AMENDMENTS HAVE BEEN RECEIVED PRIOR TO SUBMISSION OF THE BID. IN CASE ANY BIDDER FAILS TO ACKNOWLEDGE RECEIPTS OF ANY SUCH AMENDMENTS IN THE SPACE PROVIDED ON THE BID FORM, THE BID WILL NEVERTHELESS BE CONSTRUED AS THOUGH THE AMENDMENTS HAVE BEEN RECEIVED AND ACKNOWLEDGED, AND THE SUBMISSION OF THE BID WILL CONSTITUTE ACKNOWLEDGEMENT OF THE RECEIPT OF AMENDMENTS.**