

ADDENDUM #1

PROJECT: Leroy Rogers Senior Center Pavement Improvements

ACTION: Clarifications

DATE: January 8, 2018

The following clarifications are made to the above referenced project:

- 1) Based on limited site investigations, the soils in the bioretention area include 14 to 18 inches of silty sand with very clayey sands below. Bidders should anticipate undercutting 3-4 ft in the pond area and backfilling with the silty sand soils. The on-site surface soils on the site should be suitable for use as the planting media in the pond. Testing at the time of undercutting and stockpiling will be required to determine the need for soil amendments to adjust the soil pH.
- 2) The bid date remains unchanged.

All bidders shall acknowledge receipt of all addenda issued where indicated on the bid sheets.

BIDDERS ARE ADVISED THAT IT IS THEIR RESPONSIBILITY TO VERIFY THAT ANY AND ALL AMENDMENTS HAVE BEEN RECEIVED PRIOR TO SUBMISSION OF THE BID. IN CASE ANY BIDDER FAILS TO ACKNOWLEDGE RECEIPTS OF ANY SUCH AMENDMENTS IN THE SPACE PROVIDED ON THE BID FORM, THE BID WILL NEVERTHELESS BE CONSTRUED AS THOUGH THE AMENDMENTS HAVE BEEN RECEIVED AND ACKNOWLEDGED, AND THE SUBMISSION OF THE BID WILL CONSTITUTE ACKNOWLEDGEMENT OF THE RECEIPT OF AMENDMENTS.